

CLASSIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. V-11


Note: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a post was set for the corner from which:

A 10" fir bears S20°W 46 lks.  
A 20" pine bears N33°W 41 lks.

This corner was also recovered by surveyor John Kimbrell, during his County Survey No. 95, in 1897.



Corner No. \_\_\_\_\_  
Compass Declination: 19.0°

**Description of corner evidence found:**

A 30" live ponderosa pine bears N33°W 27.1', with scribes "BT" visible on open lower blaze.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At a point S33°E 27.1 feet from the found bearing tree, set a 2 1/2" brass cap on 1 1/2" by 30" galv. iron pipe, 15" in the ground and surrounded with a mound of earth and stone. From the new monument:

A 16" douglas fir bears S47°W 41.9' scribed 1/4 S33 BT.

Placed bearing object signs on each bearing tree and set a steel fence post east of corner with witness corner sign attached.

There is a fence corner 20' north and 10' east of the corner point. The fences go west and south.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

7-27-88

Office of Syracuse County of Umatilla  
State of Ore. I hereby certify that the within instrument was filed in this office  
for record on the 28<sup>th</sup> day of July, 1988  
David A. Humboldt by Kathleen K. Ambrose  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor 890-788-876  
Date 7-88  
Rec'd By [Signature]  
No. 88-42-C