

C. UNIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. V-17


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a wood post was set from which:

- A 24" pine bears S25°E 97 lks.
- A 24" pine bears S25°E 47 lks.
- A 24" pine bears N2°W 89 lks.
- A 24" pine bears N2°E 79 lks.

This corner was re-monumented by PLS 1106 in 1979. See map filed in County Surveyor's Office.



Corner No.
Compass Declination 19.0°

Description of corner evidence found:

A 3" brass cap on a 2 1/2" galv. iron pipe protruding 6" from the ground, at a fence corner with old fences going east and south from which:

A sawn 36" ponderosa pine stump bears S45°W 31.0' with scribes "BT" visible on lower blaze.

A rotted pine stump bears S25°E 64.0' with scribes rotted off.

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained existing monument by building a stone mound around it. Marked new bearing trees as follows:

- A 18" ponderosa pine bears N88°E 55.6' scribed T4N R36E S26 BT.
- A 17" ponderosa pine bears S65°E 141.1' scribed T4N R36E S35 BT.
- A 16" ponderosa pine bears N2°W 85.1' scribed T4N R36E S27BT.
- No tree available in the SW quadrant.

Attached bearing object signs to the new bearing trees and the original SW bearing tree stump. Placed a steel fence post North of corner and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1917
WILLIAM R. WELLS
1106

7-27-88

Office of Survey County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 28th day of July 1988
David H. Keumber by Kathleen L. Ambsauer
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 7-88
 Rec'd By [Signature]
 No. 88-42-C