

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

T 4N, R 36E., W.M.


Corner Code No. V-19  
Note: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a post was set from which:

- A 24" pine bears S45°W 45 lks.
- A 28" pine bears N50°W 51 lks.

In 1885, during his County Survey No. 7, surveyor Arnold reestablished the corner from the original bearing tree stumps and set a stone and bottle at the corner point. Surveyor Arnold notes that a traveled east-west road passes over the corner point.



Corner No.  
Compass Declination: 19.0°

**Description of corner evidence found:**

Old fence running north from the east-west road bed called for in County Survey No. 7. The stone set by surveyor Arnold was not found due to grading of the east-west road over the years.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Reestablished corner using the east-west road bed for latitude and the old fence approaching from the north for departure. Since the corner point falls in the east-west road bed, a witness corner monument was set South 12.00 feet from the true corner point. At the witness corner point, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 26" in the ground and surrounded with a mound of earth and stone. The witness corner cap is marked as shown in the corner diagram. From the witness corner monument:

A 18" ponderosa pine bears N14°E 67.3' scribed "X" at breast height and "BT" at base.

A 6" ponderosa pine bears S34°W 125.9' scribed "X" at breast height and "BT" at base.

Attached bearing object signs to each of the bearing trees.

Set steel fence post west of corner and attached witness corner sign. There is a fence corner 1 1/2' east of the witness corner monument. Fences go east and south from the fence corner.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

7-27-88

Office of Sheriff County of Umatilla  
State of Oregon, I hereby certify that the within instrument was filed in this office  
for record on the 28<sup>th</sup> day of July, 1988  
David H. Keabbein by Kathleen Chambers  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor OPC-700-878

Date 7-88

Rec'd By [Signature]

No. 88-42-C