

C. UNIFIED RECORD OF LAND CORNER MONUMENTATION


T 4N , R 36E. , W.M.

Corner Code No. V-21

Notes Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a post was set for the corner from which:
 a 24" fir bears N40°W 22 lks.
 a 4" fir bears S15°E 13 lks.
 a 10" fir bears S20°W 19 lks.
 a 4" willow bears N35°E 21 lks.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

Found round 1" diameter by 30 inch long rod protruding 3" from the ground. This monument has been used by surveyors Krumbain and Wells and shows on old state highway maps for the Weston-Tollgate highway. The origin of the iron rod is unknown.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the iron rod monument, set a 2 1/2" brass cap on a 1 1/2" by 30" iron pipe 24" in the ground and surrounded with a mound of earth and stone. Placed the iron rod monument inside the new monument. Referenced the new monument as follows:

A 21" white fir bears 85°E 14.5' scribed T4N R36E S36 BT.
 A 4" ponderosa pine bears N28°E 53.3' scribed "X" at breast height and "BT" at base.
 No other trees are convenient for reference. Attached bearing object sign to each of the bearing trees.

Also set a concrete nail in the south side of pole no. 269001. The nail bears N80°W 52.3' from the new monument and is about 1' above the ground. Placed bearing object sign on the pole.

Set steel fence post west of the corner monument with witness corner sign attached.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of Survey County of Umatilla 7-27-88
 State of Ore I hereby certify that the within instrument was filed in this office
 for record on the 28th day of July 1988
David H. Lusk by William R. Wells
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor 780-878

Date 7-88

Rec'd By KA

No. 88-42-C