

C E R T I F I E D R E C O R D O F L A N D C O R N E R M O N U M E N T A T I O N

T 4N, R 36E., W.M.


Corner Code No. V-7

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No 114, dated July 2, 1866. The original notes state that at the corner a wood post was set for the corner with charred stake, earth mound and pits.

In 1897, during his Co. Survey No. 95, John Kimbrell recovered the corner during his subdivision of Section 32.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

This corner position was reestablished by the method described in Section 5-36 of the 1973 "Manual of Surveying Instructions for the Survey of the Public Lands of the United States", using record bearings and distances, between the North 1/4 Corner of Section 31 and the NE Corner of Section 32 as reported in John Kimbrell's 1897 survey. At the reestablished corner position, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 14" in the ground to bedrock, and surrounded with a mound of stone. Set reference monuments to reference the new corner monument as follows:

A 1 1/2" plastic cap, marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron pin, bears N37°E 47.8'. Wired bearing object sign to the reference monument.
A 1 1/2" plastic cap, marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron pin bears N27°W 38.5'. Wired bearing object sign to the reference monument.

Set steel fence post near corner monument and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

W. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Survey County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 28th day of July 1988
David H. Kaumbel by Kathleen Ambrose
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Survey 985-780-270

Date 7-88

Rec'd By st

No. 88-42-C