


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner was originally established by William O'Dell under Contract No. 114 dated July 2, 1866. The original notes state that at the corner a wooden post was set from which:
A 30" Pine bears N89°W 115 lk (75.9 ft)
A 36" Pine bears South 300 lk (198.0 ft)




8-21

Description of corner evidence found:

No evidence of the original post was found. A 48" Ponderosa Pine with upper and lower blaze bears N89°W - 75.9 ft. Opened upper blaze and found scribe "1/4."
Searched steep slope 198 feet south of corner position and found depression shaped like that of an uprooted tree and traces of charred roots in the ground. The original BT is gone (rotted) and it is not possible to re-construct its position with any accuracy. Re-established the corner at record bearing and distance from 48" Ponderosa Pine.

Description of monument and accessories established to perpetuate the original location of this corner

At the re-established corner position a 2"x30" iron pipe with brass cap was set 2 inches in the ground and surrounded with a mound of stone. Pipe monument could not be set any deeper due to solid rock. The monument is located 1 foot south of an east-west fence and 34 feet west of a fence corner in which the fences go north-south and east-west. Established one new bearing tree:
a 20 inch Bull Pine bears S70°E 69.6 ft. scribed 1/4 S36 BT. This bearing tree also has a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush. Painted red ring around each BT.
The cap is stamped



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

This corner was set March 14, 1980.

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 27th day of March 1980
David H. Krumbein by Betty C. Slatta
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 3-27-80
Rec'd By ELS
No. R-49-M