

**OREGON CORNER RESTORATION FORM**

Section 10 Township 4N Range 37E

County Umatilla Date 6-17-94

CORNER DESIGNATION: G-13

**Previous Renewals/Surveys, etc.**

Corner originally established by U.S. Deputy Surveyor George S. Pershin under GLO contract No.332 dated July 29,1879. The Surveyor General records state: Set a basalt stone 13"x 10"x 6" on a steep N.E. face of spur for 1/4 sec.cor., from which:

A fir 12 ins. diam. brs. S 72° E 128 lks. dist.

A fir 6 ins. diam. brs. S 54° W 86 lks. dist.

**Monument(s) & Accessories Found: (Condition and Source)**

A 24" Douglas fir with a healed blaze bears S 54° W, 56.8 ft. (86 lks). After opening tree we found scribing. No evidence of basalt corner stone was found.

**Monument Detail:**

T4N R37E  
1/4  
S 9 | S 10  
1994  
PLS 1106

**Monument Set (Procedures and Description):**

At position established by reversed record bearing and distance from the recovered Section 9 bearing tree (N 54° E., 56.8 feet (86 lks.)), set a 5/8"x 15" rebar 4" in concreted hole drilled into rock. A 1 1/2"x 12" galvanized iron pipe filled with concrete is set over the rebar. Pipe has a 2 1/2" brass cap attached and is marked as shown above.

**New Accessories:**

A 18" Douglas fir that forks 10 ft. above ground bears N 17 1/2° W, 38.4 ft. and is scribed 1/4 S9 BT.

A 42" Douglas fir bears N 79° W, 129.3 ft and is scribed 1/4 S9 BT.

A 17" Douglas fir bears S 5° E, 121.7 ft. and is scribed 1/4 S10 BT.

A 9" Douglas fir bears S 58 1/2° E, 102.4 ft. and is scribed 1/4 S10 BT.

Bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached bearing object and witness signs to each tree. Painted a 6" band and face of blaze red.

Set a steel fence post S 41° E, 23.5 ft. from monument with witness corner sign attached.

**Location & Comments:** Corner is located on a steep North slope above the South Fork of the Walla Walla River.

**Compass Declination:** 18° E

Surveyor's Seal

**Firm/agency:** Tomkins-Wells Joint Venture  
Land Surveying  
P.O. Box 1696  
Pendleton, Oregon 97801

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Willi R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6/30/96*

**Party Chief:** Greg Flowers

**Notes:** Greg Flowers

**Witness:** Todd Rosenbalm

RECEIVED BY

Umatilla County Surveyor

Date 7-95

Rec'd By KK

No. 95-117-C