

OREGON CORNER RESTORATION FORM

Section 10 Township 4N Range 37E

County Umatilla Date 6-8-94

CORNER DESIGNATION: J-13

Previous Renewals/Surveys, etc.

Corner was originally set by U.S. Deputy Surveyor George S. Pershin under GLO contract No.332, dated July 29,1879. The Surveyor General records state: Set a basalt stone 17"x 12"x 8" on the West side spur for corner to Sections 9,10,15 and 16 from which:
A fir 12 ins. diam. brs. N 30° E 112 lks.dist.
A fir 9 ins. diam. brs. S 74° W 120 lks.dist.

Monument(s) & Accessories Found: (Condition and Source)

Found a 28" Douglas fir with a healed blaze, bears N 30° E, 73.9 ft. (112 lks). Could not find any scribing after opening blaze. A stump hole bears S 74° W 79.2 ft, with tree is completely deteriorated. There is no evidence of the basalt stone. I accept the recovered Douglas fir as the original Section 10 bearing tree because of the relationship of the reestablished corner position from it to found corners to the North, South, East and West and because of its relationship with found stump hole.

Monument Detail: T4N R37E

S9 | S10

S16 | S15

1994
PLS 1106

Monument Set (Procedures and Description):

At record position of S 30° W, 73.9 feet (112 lks), from the found Section 10 bearing tree, set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe 28" in the ground with a surrounding mound of earth and stone to cap. Brass cap is marked as shown above.

New Accessories:

- A 28" Douglas fir bears N 80 1/2° W, 19.3 ft. and is scribed: T4N R37E S9 BT.
- A 15" Douglas fir bears S 26 1/2° E, 13.6 ft. and is scribed: T4N R37E S15 BT.
- A 15" Douglas fir bears N 52 1/2° E, 26.1 ft. and is scribed: T4N R37E S10 BT.
- A 12" Douglas fir bears S 74 1/2° W, 37.3 ft. and is scribed: T4N R37E S16 BT.

All bearing trees have a six inch red band painted around them and a brass washer which reads PLS 1106 and bearing object and witness signs attached. Set a steel fence post 3 feet North of monument with witness corner sign attached.

Location & Comments: Corner is located on a steep West slope in brush and heavy timber.

Compass Declination: 18° E

Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Greg Flowers
Notes: Greg Flowers
Witness: Todd Rosenbalm Umatilla County Surveyor

RECEIVED BY
Date 7-95
Rec'd By KK
No. 95-117-C

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will: R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6/30/96