

OREGON CORNER RESTORATION FORM

Section 10 Township 4N Range 37E

County Umatilla Date 3/18/94

CORNER DESIGNATION: J-17

Previous Renewals/Surveys, etc.

Corner originally established by Charles L. and William C. Campbell under GLO contract number 733, dated March 22, 1901. Surveyor General records state: Set an ironstone, 15 x 12 x 8 ins., 10 ins. in the ground struck rock, raised mound of stone around for Cor. of Secs. 10, 11, 14 and 15, marked with 4 notches on the S. and 2 notches on E. edges, from which:

A fir, 36 ins. diam. brs. S. 38° W., 81 lks. dist. marked T. 4 N., R. 37 E., S. 15 B T.

A fir, 30 ins. diam. brs. N. 20° W., 18 lks. dist. marked T 4 N., R.37 E., S. 10 B T.

No other trees in limits. Mound and pits impracticable on account of steep slope.

Monument(s) & Accessories Found: (Condition and Source)

Found a scattered mound of stone on a steep South slope from which a rotted fir stump and log with visible scribes bears N 20° W, 11.9 feet (18 lks). A rotted fir stump with axe marks bears S 38° W, 53.5 feet (81 lks). This stump has broken loose and rolled down the hill.

Monument Detail:

Note: This corner applies to Sections 10 & 15 only.

T4N R37E
S10 |
-----|S11
S15 |
1994
PLS 1106

Monument Set (Procedures and Description)

At position in scattered rock mound established by reversed record bearing and distance from the recovered original Section 10 bearing tree (S 20° E, 11.9 feet), set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 24" in the ground with a surrounding mound of earth and stone to cap. Brass cap marked as shown above.

New Accessories:

A 5/8" x 30" rebar with a yellow cap stamped "WR WELLS PLS 1106" and a brass washer stamped "PLS 1106" attached bears S 17° E, 14.2 ft.

A 5/8" x 30" rebar with a yellow cap stamped "WR WELLS PLS 1106" and a brass washer stamped "PLS 1106" attached bears N 50° E, 14.1 ft.

A 40" Douglas fir bears S 47° W, 77.3 ft. marked T4N R37E S15 BT.

A 27" Douglas fir bears N 73 1/2° W, 157.3 ft. marked T4N R37E S10 BT.

All bearing trees have a brass washer stamped "PLS 1106" nailed to the face of the blaze. Attached bearing object and witness signs to each tree. Painted a 6" band and face of blaze red.

Set a steel fence post with witness sign attached alongside each rebar and 4 feet North of corner monument.

Location & Comments: The corner is about 150' North of the South Fork of the Walla Walla River Road.

Compass Declination: 18° E

Surveyor's Seal

Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Party Chief: Greg Flowers
Notes: Greg Flowers
Witness: Todd Rosenbalm

RECEIVED BY

Umatilla County Surveyor

Date 7-95

Rec'd by KK

No. 95-117-C

renews 6/30/96