

OREGON CORNER RESTORATION FORM

Section: 11, 12, 13 and 14

Township: 4N

Range: 37 EWM

County: Umatilla

Date: 03/01/00

Corner Designation: J-21, corner common to Sections 11, 12, 13 and 14

Previous Renewals/Surveys, etc.: This corner was originally set by U.S. Deputy surveyors, Charles L. and William C. Campbell, under Contract No. 733. Dated March 22, 1901. The Surveyor General's notes state: "Set an ironstone 30 x 15 x 6 ins. 22 1/2 ins. in the ground for cor. of Secs. 11, 12, 13 & 14, marked 4 notches on the S. and 1 notch on E. edges; raised mound of stone 4 ft. base, 3 ft. high W. of Cor; Pits impracticable.

Monument(s) & Accessories Found (Condition & Source): Found the remains of a 4 foot diameter stone mound per the original survey, a rock 16" x 30" x 5" was laying on the surface 20'± East (down hill) from the mound.

Monument Detail: T4N R37E

S11 S12
+
S14 S13
2000
PLS 2820

Monument Set (Procedures & Description): At the location of the found mound of stone set a 1 1/2" galvanized iron pipe with a 2 1/2" brass cap stamped as noted, 26 inches in the ground and surrounded with a mound of earth and stone.

New Accessories: A steel fence post with a land survey monument sign was placed 3.0' North of the corner. 5/8" x 30" rebar reference monuments with a yellow plastic cap stamped "TOMKINS SURVEYING" attached were set 28" in the ground, a steel fence post with a Umatilla County Bearing Object sign attached were set alongside each R.M. The reference monuments (R.M.) bear from the corners as follows:

- N54°E 20.15 FEET
- S31°E 17.37 FEET
- S41°W 15.96 FEET
- N2°W 17.90 FEET

Location & Comments: The corner falls on a steep Easterly facing slope 700'± North and 500' higher than the South Fork of the Walla Walla River.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204
Walla Walla WA 99362

Party Chief: Greg E. Flowers

Notes: Greg E. Flowers

Witness: Joshua R. Martin

Surveyor's Seal



Greg E. Flowers



RENEWS 12/31/01

12/15/00

RECEIVED BY
Umatilla County Surveyor
Date 12-00
Rec'd By SM
No. 00-254-C