

OREGON CORNER RESTORATION FORM

Section: 13 & 14

Township: 4 North

Range: 37 East, W.M.

County: Umatilla

Date: 08/14/2000

Corner Designation: L -21, 1/4 corner common to Sections 13 & 14

Previous Renewals/Surveys, etc.: This corner was originally set by U.S. Deputy Surveyors, Charles L. and William C. Campbell, under their contract No. 733 dated March 22, 1901. The Surveyor General's notes state "the point for 1/4 Sec. Cor. falls on a ledge, 2x2x1 ft. above ground. I mark a cross at the exact cor. point, for 1/4 Sec. Cor. and mark 1/4 on W. side of cross, from which: A fir, 10 ins. diam. brs. S82°30'E, 42 lks. dist., marked 1/4 S 13 BT. A fir 8 ins. diam. brs. N7°W, 21 lks. dist. marked 1/4 S14 BT.

Monument(s) & Accessories Found (Condition & Source): No evidence of the original corner could be found.

Monument Detail: T4N R37E

1/4

S14 + S13

2000

LS 2820

Monument Set (Procedures & Description): At the position determined by survey, set a 1"x 30" galvanized iron pipe 28" in the ground with a 2 1/2" brass cap attached.

New Accessories: Set 6' steel fence post 3' North of the corner. A 16" ponderosa pine bears N8°E 36.0 feet marked 1/4 S13 BT. A 16" ponderosa pine bears S15°E 40.0 feet marked 1/4 S13 BT. A 5/8"x30" rebar (RM) with a yellow plastic cap stamped "TOMKINS SURVEYING" bears S90°W 10.0 feet. A 24" ponderosa pine bears N28°W 25.0 feet marked 1/4 S14 BT.

All bearing trees have a 6" wide red band painted around them and bearing object signs attached.

The reference monuments (RM) have a steel fence post with a bearing object sign attached set alongside.

Location & Comments: This corner is located on a steep, Northeasterly facing slope at the base of a 10' high rock bluff overlooking Tamarack Basin.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204

Walla Walla WA 99362

Party Chief: Josh Martin

Notes: Josh Martin

Witness: Ryan Laughery

Surveyor's Seal



RENEWS 12/31/01

12/15/00

RECEIVED BY

Umatilla County Surveyor

Date 12-00

Rec'd by SIM

No. 00-250-C