

OREGON CORNER RESTORATION FORM

Section: 13 & 224

Township: 4 North

Range: 37 East

County: Umatilla

Date: 09/08/00

Corner Designation: N-23, 1/4 corner common to Sections 13 & 24

Renewals/Surveys, etc.: This corner was originally set by U.S. Deputy surveyors, Charles L. and William C. Campbell, under Contract No. 733, dated March 22, 1901. The Surveyor General's notes state "set an ironstone 24x15x8 ins., 18 ins., in the ground for 1/4 sec. cor., marked 1/4 on the N. face. From which a tamarack 12 ins. diam., bears S65°W, 20 lks., dist., marked 1/4 S 24 BT. A tamarack, 10 ins., diam., bears N58°W, 24 lks., dist., marked 1/4 S 13 BT".

Monument(s) & Accessories Found (Condition & Source): Found a basalt stone 24x15x8 marked 1/4 on the North side, firmly set 20" in the ground, from which a mostly rotted tamarack stump with visible scribes bears N58°W 15.8 feet and a down 12" tamarack with visible scribes bears S65°W 13.2 feet. A dead 8" fir with a healed blaze and location poster bears N89°W 15 feet.

Monument Detail: T4N R37E

S13  
1/4 +  
S24  
2000  
PLS 2820

Monument Set (Procedures & Description): At the location of the found original stone, set a 1"x 30" galvanized iron pipe with a 2 1/2" brass cap marked as shown, 22" in the ground and surrounded with a mound of earth and stone. I buried the original stone on the South side of the monument with the 1/4 facing South. Set a 6 foot steel fence post with a survey monument sign attached 1.8 feet west of the corner.

New Accessories: A 16" Douglas fir bears N61°E 31.8 feet, marked 1/4 S13 BT.

A 14" white fir bears S28°W 12.3 feet, marked 1/4 S 24 BT.

A 12" white fir with a crooked stump, bears N50°W 20.0 feet marked 1/4 S13 BT.

A 4" Douglas fir bears N5°W 19.2 feet, marked "X" at breast height.

All bearing trees have bearing tree signs and land corner monument signs attached. A 6" red band is painted around each bearing tree.

Location & Comments: This corner is located on a brushy East slope 18 feet West of a small stream 300 feet ± South of Tamarack Basin and is 15 feet higher than the stream.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204  
Walla Walla WA 99362

Party Chief: Greg Flowers

Notes: Greg Flowers

Witness: Brianna Slater

Surveyor's Seal



RENEWS 12/31/01

RECEIVED BY

Umatilla County Surveyor

Date 12-00

Rec'd By SIM

No. 00-256-C

12/15/00