

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. R-25

Notes: Monument marked as shown below.


History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor under Contract No. 114, dated July 2, 1866. The original notes state:

Set post corner for Secs. 24, 25, 19 and 30, on level in edge of pine grove, from which:

A pine, 24 ins. diam. brs S 85° W, 39 1/2 ks.
 A pine, 24 ins. diam. brs N 85° E, 29 1/2 ks.
 A pine, 15 ins. diam. brs N 75° E, 36 1/2 ks.
 A pine, 20 ins. diam. brs S 12° E, 21 1/2 ks.

As reported on Survey No. F-25-AX, dated in 1969, a stone with a cross on top was found and accepted as the perpetuation of the corner.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found basalt stone, 20"x9"x5" with "X" on top as reported in Survey F-25-AX. Stone had been tipped on it's side. Re-established stone position by holding distance of 5291.94' from the S.E. corner of Section 19 and measuring 13.9' from ponderosa pine as noted in Survey F-25-AX.

The ponderosa pine noted in Survey F-25-AX is a 45" tree with what appear to be blaze faces facing Northwest and Southeast. Upon opening these blazes, I find nothing but fencing scars. Ring count on tree indicates an age of about 110 years, therefore, the tree is not an original bearing tree. I find no evidence of any original bearing tree remains in this area.

I accept the position of the basalt stone with the "X" on top as the best remaining evidence of the original location of the corner. There is a East-West fenceline about 14' North of this stone and the remains of old fences running North and South through the position of the stone.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe 24" in ground and surrounded with a mound of earth and stone. Placed corner stone on North side of monument in new mound.

Set a steel fence post North of corner and attached a Witness Corner sign.

New bearing trees:

A 7" ponderosa pine bears N 40°E - 22.1', scribed T4NR37ES19BT.
 A 12" ponderosa pine bears S 75°E - 40.2', scribed T4NR37ES30BT.
 A 12" ponderosa pine bears S 58° 1/2 W - 71.8', scribed T4NR36ES25BT.
 A 8" ponderosa pine bears N53 1/2°W - 34.8', scribed T4NR36ES24BT.

Nailed Bearing Object signs to each tree.

REGISTERED PROFESSIONAL LAND SURVEYOR <i>William R. Wells</i> OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 7-92
 Rec'd By JK
 No. 92-99-B

☆ GPO-799-276