


History of original corner establishment:

Original survey was made by George S. Pershin under contract No. 332, dated July 29, 1879. He set a basalt stone, 14 x 12 x 4 on the west point of a spur ridge for the 1/4 sec. cor. marked 1/4 on the North face. He set the following bearing trees:
A fir 10" dia. bears N 53 W, 82 lks. dist.
A fir 20" dia. bears S 36 W, 108 lks. dist.



Description of corner evidence found:

I found a basalt stone 14 x 12 x 4 with 1/4 marked on the face.
I found a deadfir snag approx. 15" dia. with 1/4 S BT scribing visible bearing N 53 W, 82 lks. dist. from assumed corner location.
I found a fir stump approx. 25" dia. that fit the GLO call of S 36 W, 108 lks. dist. though the tree had been cut below the scribing.

Description of monument and accessories established to perpetuate the original location of this corner:

Using the evidence found, I then reset the stone in the center of a mound of stone, using the GLO bearings and distances from the verified bearing trees.
I set no new bearing trees though there should be new trees set as the original bearing trees are in poor condition.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1998
DOUGLAS M. FERGUSON
848

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of..... 19.....
..... by
(COUNTY OFFICER) (DEPUTY)