


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original survey was made by George Pershin under contract No. 332, dated July 29, 1879. The corner was set Aug. 20, 1879. He set a fir post on N. descent for section corner from which he set the following bearing trees:
A fir 8" dia. bears N 34 E, 28 lks.
A tamarack 22" dia. bears S 14 E, 63 lks.
A fir 6" dia. bears S 30 W, 36 lks.
A fir 15" dia. bears N 28 W, 22 lks.



Description of corner evidence found:

I found a badly rotted tamarack stump that fit the description of the tamarack bearing S 14 E, 63 lks. I found no evidence of the fir bearing trees. This area is predominantly white fir and thus the dead trees or stumps deteriorate very rapidly. Also the area has been logged at least twice since the original corner was established in 1879.

Description of monument and accessories established to perpetuate the original location of this corner

After tying the position of the badly rotted tamarack stump into our extensive co-ordinate system, I determined that this was actually one of the original bearing trees and thus used it as collateral evidence for the position of the original corner from which I reset the section corner using the GLO calls, placing a 5/8" by 30" steel pin with a plastic cap stamped LS 645, in a mound of stone with the following new bearing trees:

- A spruce 8" dia. bears N 66 00 E, 38.67 ft. and being scribed T 4 N R 37 E S 22 BT.
- A white fir 9" dia. bears S 58 30 E, 52.37 ft. and being scribed T 4 N R 37 E S 27 BT.
- A spruce 9" dia. bears S 72 30 W, 59.70 ft. and being scribed T 4 N R 37 E S 28 BT.
- A spruce 13" dia. bears N 43 30 W, 87.46 ft. and being scribed T 4 N R 37 E S 21 BT.

Note: The above described evidence was found by PLS 645. Then found and used by me PLS 848 as controlling corners to the accompanying map of survey.

REGISTERED PROFESSIONAL LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Office of County of
State of I hereby certify that the within instrument was filed in this office for record on the day of
..... by
(COUNTY OFFICIAL) (DEPUTY)