

OREGON CORNER RESTORATION FORM

Section 27 Township 4N Range 37E W.M.
County Umatilla Date 8-1-93
CORNER DESIGNATION:R-15

Previous Renewals/Surveys, etc.: The original survey was made by George S. Pershin under contract No. 332, dated July 29th, 1879. He set a fir post on N.W. slope for 1/4 Sec. Corner from which:
A fir, 10" in diameter bears N. 50°E., 45 lks. dist.
A fir, 6" in diameter bears S. 28°W., 35 lks. dist.
Map No. N-65 indicates that Hambleton found evidence of the original G.L.O. corner in 1977.

Monument(s) & Accessories Found: (Condition and Source)
Found a wagon axle skein in a mound of stone, from which a rotten stump with axe marks and scribing bears S. 30°W. 23.4'.
A 6" spruce with a Boise Cascade Location Sign bears S. 24°W. 2'.
A steel fence post bears West 1.0'.

Monument Detail:

T4N R37E

$\frac{1}{4}$

4

S 22

S 27

1993

LS 1106

Monument Set (Procedures and Description): Set 1 1/2" x 30" iron pipe with a 2" brass cap stamped as indicated in the monument detail, 25" in the ground in place of the axle skein, set the spinit beside the monument as a witness. No record of the origin of the axle spinit was found.

New Accessories:

A 10" fir bears S. 85°W. 10.0'.
A 14" fir bears N. 18°W. 24.1'.
A 7" fir bears S. 88°E. 13.6'.
A 8" fir bears S. 14°E. 22.2'.

Location & Comments: The corner is located in a thicket approximately 200' S.E. of a stock pond.

Compass Declination: 18°E
Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12-31-94

Party Chief: Greg Flowers
Notes: Greg Flowers
Witness: Todd Rosenbalm

93-64-C