

**OREGON CORNER RESTORATION FORM**

Section 22,23,26 27 Township 4N Range 37E W.M.  
County Umatilla Date 8/1/93  
CORNER DESIGNATION: R-17

Previous Renewals/Surveys, etc. The original survey was made by George S. Pershin under contract No. 332, dated July 29th, 1879. He set a fir post on level for Cor. to Sec. 22,23,26,27.

A Pine, 18" in diam bears N.26°E., 90 lks. dist.  
A fir, 6" in diam. bears S.34°E., 58 lks. dist.  
A fir, 10" in diam bears S.50°W., 108 lks. dist.  
A tamarack, 5" in diam. bears N.28°W., 131 lks. dist.

Monument(s) & Accessories Found: (Condition and Source) Found a wagon axle skein and a 5/8" rebar with a plastic cap stamped LS 645 set in a mound of stone. From which:

A 18" pine, with visible scribing (T4N R37E S24 X BT) with a nail in the X, bears N.73°E., 67.2 ft. to the nail.  
A 15" fir, with healed a blaze bears S.57°E., 22.9 ft.  
A 16" fir with a healed blaze bears S.43 1/2°W., 57.2 ft.  
A 14" tamarack with visible scribing(T4N R37E S 22 X BT) with a nail in the X, bears N.24 1/2°W., 85.5 ft. to the nail.

Monument Detail:

T4N R37E

S22 | S23

+

S27 | S26

1993

OR 1106

Monument Set (Procedures and Description): Set a 1 1/2" x 30" iron pipe with a 2 1/2" brass cap marked as indicated in the monument detail, 24" in the ground at the location of the axle skein, and 5/8" rebar. The pine and the tamarack don't appear to be the original bearing trees because the style of scribing and the nail in the x are not similar to that found on other corners. The only record that was found was on a map of survey filed by James Hambleton, dated, 2/15/77, (file No. N-65 Umatilla County Records) in which he indicates that he found the original GLO corner.

New Accessories: A steel fence post bears N. 3.0 ft. with a Land Survey Monument sign attached.

Location & Comments: The corner is on the level about 200' E. of the Linton Mtn. road.

Compass Declination: 18° E  
Firm/agency: Tomkins-Wells Joint Venture  
Land Surveying  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Greg Flowers  
Notes: Greg Flowers  
Witness: Todd Rosenbalm

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

expires 12-31-94

93-64-C