

OREGON CORNER RESTORATION FORM

Section 20,21,28,29 Township 4N Range 37E W.M.
County Umatilla Date 8/1/93
CORNER DESIGNATION: R-9

Previous Renewals/Surveys, etc. The original survey was made by William Odell under contract No. 114, dated July 2nd, 1866. He set a post Cor. for Secs. 20,21,28 & 29, from which :

A fir, 12 ins. diam.brs. N.36°E., 70 lks dist. A fir, 15 ins. diam. brs. N.47°W., 30 lks. A larch, 20 ins. diam. brs. S.35°W., 25 lks.
A fir, 10 ins. diam. brs. S.61°E., 40 lks.

George S. Pershin under contract No. 332, dated July 29th, 1879, searched for this corner in order to survey the N. line of sec. 28 but could find no trace of it, so he re-established it from the found 1/4 cor. to the south. He set a tamarack post on E. face of bluff for Cor. to Secs. 20,21,28, & 29 from which. A tamarack, 4 ins. diam. brs. N.57°E., 67 lks. dist. A fir, 20 ins. diam. brs. S.58°E., 74 lks. dist. A fir, 4 ins. diam. brs. S.70°W., 28 lks. dist. A fir, 14 ins. diam. brs. N.44°W., 62 lks. dist.

Per Land Corner Record Q-722 of Umatilla County Douglas Ferguson set a 1/2" rebar in a mound of stone, from which:

A Tamarack stump with BT scribed on its face brs. N.57°E., 67 lks. dist.

A fir stump with BT scribed on its face brs. S.70°W., 28 lks dist.

A fir stump with BT scribed on its face brs. W.44°W., 62 lks dist.

Monument(s) & Accessories Found: (Condition and Source) Found a 1 1/2" iron pipe with a 2 1/2" brass cap in a mound of stone, the cap was marked T4N R37E S20,S21,S28,S29, 1977, ORE 422 from which:

A 18" stump marked BT brs. N.46°W., 41.1 ft.

A 12" stump marked BT brs. N.56°E., 50.4 ft.

A 16" stump marked BT brs. S.66°W., 13.9 ft., this stump has been pushed out of a skid trail by logging operations.

Monument Detail:

T4N R37E
S20 | S21
S29 | S28
1977 ORE 422

Monument Set (Procedures and Description): I maintained the found monument by clearing away the brush and rebuilding the rock mound.

New Accessories:

A 10" fir brs. N.25°W., 51.6 ft. marked T4N R37E S20 BT.

A 17" fir brs. N.38°E., 11.8 ft. marked T4N R37E S21 BT.

A 18" fir brs. S.38°W., 63.4 ft. marked T4N R37E S29 BT.

A 14" fir brs. S.23°E., 54.8 ft. marked T4N R37E S28 BT.

A steel fence post with a Land Survey Monument sign attached brs. W. 2 ft.
Location & Comments: The corner is on a East slope 100' East of a N., S. fence.

Compass Declination: 18° E

Surveyor's Seal

Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Greg Flowers

Notes: Greg Flowers

Witness: Todd Rosenbalm

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12-31-94

93-64-C