

OREGON CORNER RESTORATION FORM

Section 29,30 Township 4N Range 37E  
County Umatilla Date 8/1/93  
CORNER DESIGNATION: T-5

Previous Renewals/Surveys, etc. The original survey was made by William Odell under contract No. 114, dated July 2nd, 1866. He made the corner on a White fir, 12 ins. diam. from which,  
A fir, 8 ins. diam. brs. N.5°W., 16 lks.  
A larch, 7 ins. diam. brs. S.30°E., 6 lks.

Monument(s) & Accessories Found: (Condition and Source) Found a 1 1/2" iron pipe with a 3 1/2" brass cap 10" above ground at the intersection of a fence running N. S. & E. no other evidence found, the area has been logged. No history of the brass cap was found.

Monument Detail:

T4N R37E  
S30 | S29  
1  
4  
1977 CE 5408

Monument Set (Procedures and Description): The monument was solidly set and in good condition.

New Accessories:

A 8" fir brs. S.11°W., 9.1 ft. marked T4N R37E S30 BT  
A 14" fir brs. N.31°W., 14.1 ft. marked T4N R37E S30 BT  
A 7" fir brs. N.81°E., 9.2 ft. marked T4N R37E S29 BT  
A 7" fir brs. S.47°E., 36.7 ft. marked T4N R37E S29 BT  
A steel fence post with a Land Survey Monument sign attached brs. N. 3.6 ft. in a N.S. fence line.

Location & Comments: The corner is on the level 1300' S. of the Basket Mtn. road.

Compass Declination: 18° E  
Firm/agency: Tomkins-Wells Joint Venture  
Land Surveying  
P.O. Box 1696  
Pendleton, Oregon 97801

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*expires 12-31-94*

93-64-C