

OREGON CORNER RESTORATION FORM

Section 28,29 Township 4N Range 37E W.M.
County Umatilla Date 8/1/93
CORNER DESIGNATION: T-9

Previous Renewals/Surveys, etc. The original Survey was made by William H. Odell, under contract No. 114, dated July 2nd, 1866. He set a fir post for 1/4 Sec., from which:
A fir 12" in diam. bears N.15°W., 10 lks. dist.
A fir 14" in diam. bears S.20°E., 17 lks. dist.
Land Corner Record Q-725 shows that Douglas M. Fegison found a 1" iron pin 3" below the ground and evidence of the original BT's.

Monument(s) & Accessories Found: (Condition and Source) Found a 1"x 28" axle shaft 6" below the ground, from which a 36" fir stump with scribing(1/4s) visible, bears N.24°W., 7.5 ft. this is approximately 8' long and has fallen over.
A rotted stump bears S.44°E., 10.6 ft.

Monument Detail:

T4N R37E
1/4
S29 | S28
1993
OR 1106

Monument Set (Procedures and Description): Set a 1 1/2"x 30" iron pipe with a 2 1/2" brass cap stamped as indicated in the monument detail 6" below the ground.

New Accessories: A 4" fir bears S.9 1/2°W., 21.8 ft. scribed, T4N R37E S29 BT.
A 5/8" rebar with a yellow plastic cap stamped WR WELLS PLS 1106 set 34" in the ground at the south edge of a railroad tie fence corner post bears, N.24°W., 5.0 ft.
A 7" fir scribed T4N R37E S 28 BT bears, N.31 1/2°E., 36.9 ft.
A 7" fir scribed T4N R37E S 28 BT bears, S.70°E., 14.8 ft.
A railroad tie fence corner post with Land Survey Monument sign attached bears N.24°W., 5.5 ft.


Location & Comments: The corner is about 1300' N. of state highway 204 and 150' east of a house.

Compass Declination: 18° E
Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

Surveyor's Seal



William R. Wells



expires 12-31-94

Party Chief: Greg Flowers
Notes: Greg Flowers
Witness: Todd Rosenbalm

93-64-C