

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. V-11

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 322, dated July 29, 1877.


The original notes state:

Set tamarack post on SW face of hill for 1/4 Section corner from which:

A tamarack 10 in. di. brs N 34° W 34 lks dist.
A tamarack 8 in. di. brs S 50° E 12 lks dist.

In 1976, an original bearing tree for this corner was recovered as noted on Survey No. N-115-B.

In 1978, the NW original bearing tree was recovered and the corner re-monumented as noted on corner Certificate Q-729.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 2 1/2" brass cap on a 2 1/2" galvanized iron pipe, set flush with the ground from which:

A 14" white fir bears N 14° W, 21.37' with partly healed blaze.
A 12" white fir bears S 64° E, 26.83' with partly healed blaze.

The bearing trees noted above were marked by Douglas M. Ferguson as noted on corner certificate Q-729. These bearing trees have USFS bearing tree signs attached.

Description of monument and accessories I established to perpetuate the original location of this corner:

Cleaned up debris around the existing monument and set steel fence post West of corner and attached witness corner sign.

Marked two new bearing trees:

A 16" douglas fir bears N 37 1/2° E, 45.1' scribed 1/4 S28 BT.
A 7" white fir bears S 54° E, 13.7' scribed 1/4 S33 BT.

Attached bearing object signs to the new bearing trees.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)
(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-9/

Rec'd By [Signature]

No. 91-25-C

☆ GPO-788-276