


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

(10)

**History of original corner establishment:**

The original survey was made by George S. Pershin under contract No. 332, dated July 29, 1879. He set a fir post in a small open glade for the  $\frac{1}{4}$  sec. cor. on a South-west hillside. He set the following bearing trees:  
A fir 13" dia. bears N 34 E, 81 lks.  
A fir 24" dia. bears S 46 W, 111 lks.



**Description of corner evidence found:**

I found the small open glade with the bearing trees at its edges though I did not find any evidence of the wooden post.  
I found evidence of a fir 13 in. dia. bears N 34 E, 81 lks. from assumed corner location with the face blaze partially exposed with scribing visible.

**Description of monument and accessories I established to perpetuate the original location of this corner**

I set a small mound of stone at the position of the  $\frac{1}{4}$  corner by using the GLO bearings and distances from the original bearing trees. I did not set any new bearing trees though there should be some set.



Office of ..... County of .....

State of ....., I hereby certify that the within instrument was filed in this office  
for record on the ..... day of .....

..... by .....

(COUNTY OFFICIAL) (DEPUTY)