

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. V-5

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by W.H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866.

The original notes state:

Corner for sections 29, 30, 31, & 32 is a larch tree 18 in. dia. from which:

- A fir 20 in. dia. bears N 80° E, 40 links.
- A fir 24 in. dia. bears S 45° E, 16 links.
- A fir 6 in. dia. bears S 73° W, 40 links.
- A fir 10 in. dia. bears N 50° W, 33 links.

NOTE: The corner position is now marked by a railroad spike 1 1/2" below the paved road surface. This railroad spike has been used on all recent surveys as the section corner.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found a railroad spike for the corner from which:

- A 28" Englemann spruce bears N 79° 52' W, 63.6', with scribing visible on partly healed blaze.
- A 14" western larch bears N 35° 44' E, 55.5', with scribing visible on partly healed blaze.
- A 1/2" iron pin bears S 00° 23' 03" W, 41.01'.

Description of monument and accessories established to perpetuate the original location of this corner:

Due to traffic on the Weston-Elgin highway, this corner was not remonumented.

Set 2 new bearing objects:

- A 5/8" iron pin with a 1 1/2" yellow plastic cap marked "W.R. Wells, PLS 1106" bears N 84° 57' 01" E, 224.00'.
- A 5/8" iron pin with a 1 1/2" yellow plastic cap marked "W.R. Wells, PLS 1106" bears S 57° 40' 43" W, 139.53'.

Placed bearing object signs on old bearing trees and near new pins.

Set a steel fence post in fence line S 12° E, 40.0' from corner, and attached a witness corner sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 9-91

Rec'd By KK

No. 91-75-C