


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

6

History of original corner establishment:

Original survey was made by Wm. H. Odell, US Deputy Surveyor, under contract No. 114, dated July 2, 1866. He set a post for the $\frac{1}{4}$ cor. common to Sections 29 & 32. He set the following bearing trees:
A larch 20" dia. bears N 20 W, 22 lks.
A larch 18" dia. bears S 25 E, 30 lks.



Description of corner evidence found:

I found a set stone at a fence corner and two bearing trees of which are of record and can be found in the files of the Umatilla County Surveyors office. This evidence is a perpetuation of the original $\frac{1}{4}$ corner set by Wm. H. Odell in 1866.

Since the location of the stone is harmonious with surrounding evidence and it is probable that the stone was set as a perpetuation in a 1906 retracement of the original corners in the area, I accepted position of the stone as the original corner location.

Description of monument and accessories I established to perpetuate the original location of this corner

None



Office of County of

State of, I hereby certify that the within instrument was filed in this office
for record on the day of

..... by

(COUNTY OFFICIAL) (DEPUTY)