


History of original corner establishment:

Original survey was made by Wm. H. Odell, Deputy Surveyor under contract No. 114, dated July 2, 1866. He set a post for the section corner common to 28, 29 & 32, 33. He set the following bearing trees:
 A fir 8" dia. bears S 68 W, 27 lks.
 A fir 8" dia. bears S 75 E, 21 lks.
 A fir 20" dia. bears N 30 W, 52 lks.
 A fir 8" dia. bears N 20 E, 56 lks.



Description of corner evidence found:

I found no trace of this corner nor its bearing trees. The area around this section corner has been cleared or logged very heavy many years ago and thus left no trace of the original corner; some trees are growing back, but most of the area is still a meadow.

Description of monument and accessories I established to perpetuate the original location of this corner:

After an extensive search and making ties to the original GLO calls to a spring branch nearby, I determined the corner to be a lost corner, thus I re-established the corner position by proportionate measurements and set a 2" galv. iron pipe with a 2 1/2" brass cap at the position determined to be the section corner common to Sections 28, 29 & 32, 33 from which I set the following new bearing trees:
 A 9" fir bears S 37 W, 48.91 feet, scribed T 4 N R 37 E S 32 BT.
 A 6" spruce bears N 86 W, 61.13 ft, scribed T 4 N R 37 E S 29 BT.
 A 16" spruce bears N 26 E, 33.15 ft., scribed T 4 N R 37 E S 28 BT.
 No trees available in Section 33.

Cap Stamped
 T 4 N
 S 29 | S 28
 S 32 | S 33
 R 37 E
 1978

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR


Douglas M. Ferguson
 OREGON
 JULY 12, 1968
 DOUGLAS M. FERGUSON
 848

Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original survey was made by Wm. H. Odell, Deputy Surveyor under contract No. 114, dated July 2, 1866. He set a post for the section corner common to 28, 29 & 32, 33. He set the following bearing trees:
A fir 8" dia. bears S 68 W, 27 lks.
A fir 8" dia. bears S 75 E, 21 lks.
A fir 20" dia. bears N 30 W, 52 lks.
A fir 8" dia. bears N 20 E, 56 lks.



Description of corner evidence found:

I found no trace of this corner nor its bearing trees. The area around this section corner has been cleared or logged very heavy many years ago and thus left no trace of the original corner; some trees are growing back, but most of the area is still a meadow.

Description of monument and accessories established to perpetuate the original location of this corner:

After an extensive search and making ties to the original GLO calls to a spring branch nearby, I determined the corner to be a lost corner, thus I re-established the corner position by proportionate measurements and set a 2" galv. iron pipe with a 2 1/2" brass cap at the position determined to be the section corner common to Sections 28, 29 & 32, 33 from which I set the following new bearing trees:
A 9" fir bears S 37 W, 48.91 feet, scribed T 4 N R 37 E S 32 BT.
A 6" spruce bears N 86 W, 61.13 ft., scribed T 4 N R 37 E S 29 BT.
A 16" spruce bears N 26 E, 33.15 ft., scribed T 4 N R 37 E S 28 BT.
No trees available in Section 33.

Cap Stamped
T 4 N
S 29 | S 28
S 32 | S 33
R 37 E
1978



Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....
..... by.....
(COUNTY OFFICIAL) (DEPUTY)

Q-728