

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. X-13

Notes: Monument marked as shown below

History of original corner establishment:


This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 332, dated July 29, 1879.

The original notes state:

Set Fir post on level for 1/4 Sec. cor.

A Fir 10 in. di. brs S 74° E 19 lks. dist.  
A Fir 8 in. di. brs N 75° W 14 lks. dist.

In 1978, Douglas M. Ferguson searched for this corner and found no acceptable evidence of its original location. Ferguson re-established the corner by single proportion measurement. See corner certificate No. 4-733.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on a 2 1/2" galvanized iron pipe with top of cap set 8" below ground. The corner monument is on the South edge of a gravel road. From the found corner monument:

A 12" Englemann spruce bears N 68° E 25.67' with partly healed blaze.  
A 12" white fir bears S 38° W 96.83' with healed blaze.

The bearing trees noted above were marked by Douglas M. Ferguson, and have USFS bearing tree tags attached.

Description of monument and accessories I established to perpetuate the original location of this corner:

Recovered the corner monument, noted cap markings, then placed a mound of stone over the corner. Set steel fence post 3.2' South of monument and attached witness corner sign.

Marked two additional bearing trees:

A 18" white fir bears N 09° W 55.7' scribed 1/4 S33 BT.  
A 11" douglas fir bears S 45° W 35.9' scribed 1/4 S33 BT.

Placed bearing object signs on the two new bearing trees.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-91

Rec'd By KK

No. 91-75-25

★ GPO—798-276