


History of original corner establishment:

The original survey was made by George S. Pershin under contract No. 332, dated July 29, 1879. He set a fir post on level for the 1/4 section corner. He set the following bearing trees:  
A fir 10" dia. bears S 74 E, 19 lks. dist.  
A fir 8" dia. bears N 75 W, 14 lks. dist.



Description of corner evidence found:

After an extensive search, I found no trace of the original corner or its accessories although I did find an old stump with BT carved (not scribed) on its SW face of which I could find no record of its existence. Also I found a 1/2" iron pin about 15 ft. to the north-east of the stump. Upon further research, I found that Ralph Thompson ORLS 506 set the iron pin, stating that he had found the stump with BT carved into the SW face and that he felt the corner was on the opposite side of the tree, though he did not have evidence to base this opinion on. With this shakey type of evidence, I felt that I had no sound basis to accept the 1/2" iron pin as the actual 1/4 corner, therefore, with no acceptable evidence, I determined this to be a lost corner and re-established its position by proportionate measurements.

Description of monument and accessories I established to perpetuate the original location of this corner:

Upon determining this 1/4 corner as being lost, I used proportionate measurements to re-establish its position at which point I set a 2" galv. iron pipe with a 2 1/2" brass cap 6" below the surface and placed three large stones over the monument from which I set the following new bearing trees:

A fir 6" dia. bears S 38 W, 96.83 ft. scribed 1/4 S S33 BT.  
A spruce 9" dia. bears N 68 E, 25.67 ft. scribed 1/4 S S34 BT.

Cap Stamped

T 4 N  
1/4  
S 33 | S 34  
R 37 E  
1978

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Douglas M. Ferguson*  
OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)