

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. X-25

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878.

The original notes state:

Set fir post on nearly level for 1/4 Sec. cor. from which:

A fir 20 in di. bears S 45°E, 58 lks dist.  
A fir 26 in di. bears S 36°W, 51 lks dist.

This corner was recovered and monumented by the Oregon State Forestry Department as noted on Survey No. 84-106-B.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found a 3 3/4" aluminum State Forestry Department cap, on a 2" galvanized iron pipe, flush with ground, and 6" East of a North-South fence line, from which:

- A 46" white fir bears S 36°W, 34.5', scribes are visible on open blaze. (original bearing tree)
- A 1 1/2" O.D. iron pipe bears N 44°E, 0.45'. (origin unknown)
- A 12" douglas fir bears N 79°W, 12.2', with healed blaze. (1984 State Forestry Dept. bearing tree)
- A 10" white fir bears N 45°E, 32.4', with scribes visible on partly healed blaze. (1984 State Forestry Dept. bearing tree)

The State Forestry Department bearing trees have U.S.F.S. bearing tree signs attached.

Description of monument and accessories | established to perpetuate the original location of this corner:

Cleaned up around corner.

Marked 1 new bearing tree:

A 6" Englemann spruce bears S 45°E, 20.1', scribed 1/4 831 BT.

Placed bearing object sign on new bearing tree and one on the original bearing tree. Nailed U.S.F.S. Land Corner Monument signs to the back of all bearing trees.

Set steel fence post South of corner and attached a witness corner sign, and a U.S.F.S. National Forest boundary sign.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Painted face of blaze, and a 6" red band around each bearing tree

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-9-77

Rec'd By KR

No. 91-75-C

☆ GPO-798-276