

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. X-9

Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by W. H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866.

The original notes state: Set post corner for 1/4 section from which:

A pine 12 in dia bears N 89° W 18 lks dist.  
A fir 10 in dia bears N 81° E 26 lks dist.

No record of physical re-establishment of this corner was found in County Records.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

None. The corner area was thoroughly searched for approximately 3 hours. All evidence of the original corner and it's accessories has been erased by time and logging.

Description of monument and accessories established to perpetuate the original location of this corner:

This corner was re-established by single proportion measurement between the recovered Southeast corner of Section 32 and the N 1/16th corner common to Sections 32 and 33, established by Douglas M. Ferguson as reported in Survey No. P-113-B.

At the re-established corner position I set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, 24" in the ground and surrounded with a mound of earth.

From the re-established corner monument:

A 11" alpine fir bears S 58° W 12.3' scribed 1/4 S32 BT.  
A 11" western larch bears S 20° E 23.3' scribed 1/4 S33 BT.  
A 6" western larch bears N 59 1/2° E 21.3' scribed 1/4 S33 BT.  
A 14" white fir bears N 14° W 17.5' scribed 1/4 S32 BT.

Placed bearing object signs on all new bearing trees.

Set steel fence post North of corner and attached witness corner sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-9/

Rec'd By KE

No. 91-25-C

☆ GPO-798-276