

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N , R 37E. , W.M.

Corner Code No. Z-1

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by W.H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866.

The original notes state:

Set post corner for Townships 3 & 4 North, Ranges 36 & 37 East, Sections 1, 6, 31, & 36 from which:

- A fir 10 in dia bears N 10° W 24 lks.
- A fir 8 in dia bears N 55° E 20 lks.
- A fir 6 in dia bears S 45° E 30 lks.
- A fir 12 in dia bears S 03° W 18 lks.

In 1974, under Survey No. I-153-C, a "rock with X" was reportedly found at the corner point. All surveys since 1974 have used the marked stone as the Township corner.



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

Found a 21" by 16" by 6" stone marked "x" on top at fence corner with fences going North and East from which:

A 18" Douglas fir, with scribing visible on partly healed blaze, bears S 03 1/2° E, 34.5'. (Survey I-153-C)

A 13" western larch, with scribing visible on partly healed blaze, bears S 68 1/2° W, 44.2'. (Survey I-153-C)

Description of monument and accessories I established to perpetuate the original location of this corner:

The origin of the stone is not known, but it has been used on all recent surveys in the area. I accept the stone as the perpetuation of the original corner monument.

At the position of the "X" on the found stone, set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe 20" in ground, surrounded with a mound of earth and stone. Placed found stone on the West side of new monument. (Note: Corner stone was broken up.)

Marked 2 new bearing trees:

- A 5" Douglas fir bears N 80° E, 40.7', scribed "X" at breast height, and Bt at base.
- A 15" Douglas fir bears N 67° W, 45.3', scribed T4N R36E S36 BT.

Put bearing object signs on bearing trees.

Set steel fence post East of corner and attached witness corner sign.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 9-9-77
 Rec'd By [Signature]
 No. 91-25-C