


History of original corner establishment:

The original survey was made by George E. Pershin under contract No. 304, dated Sept. 19, 1878. He set a fir post on level for corner to Sec's 3, 4 & 33, 34. He set the following bearing trees:
 A tamarack 12" dia. bears N 34 E, 54 lks.
 A tamarack 11" dia. bears S 46 E, 20 lks.
 A fir 18" dia. bears S 52 W, 43 lks.
 A tamarack 14" dia. bears N 62 W, 31 lks.



Description of corner evidence found:

Made an extensive search in the area of this section corner. I found no trace of the original post or the bearing trees as the area has been heavily logged many years ago. However I did find a set stone which measures 24" x 10" x 4" buried 14" in the ground; I found no record of this stone being set, but due to its suspicious character, I tied the stone to my extensive co-ordinate system and finding the position to be harmonious with the surrounding evidence and found corners, I determined the stone was a perpetuation of the original section corner set by George E. Pershin in 1878.

Description of monument and accessories established to perpetuate the original location of this corner:

None



Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)