

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N , R 37E. , W.M.

Corner Code No. Z-7

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by W.H. Odell, U.S. Deputy Surveyor, under Contract No. 214, dated July 2, 1866.

The original notes state:

Set post corner for 1/4 section from which:

A pine 8 in dia bears N 12° W 22 links.
A fir 6 in dia bears S 15° W 27 links.

In 1974, under Survey No. I-153-C, a rock with "X" was reportedly set at the re-established corner position.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 14" by 9" by 4" above ground stone with cross, which bears S 21° 59' E, 18.09' from corner position as re-established by this survey. This stone is from Survey I-153-C, and was rejected because it is out of position.

Description of monument and accessories | established to perpetuate the original location of this corner:

Re-established corner by single proportion measurement between the Southwest corner of Section 31, and the Southeast corner of Section 32, and set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe 24" in ground, and surrounded with a mound of earth and stone

From the new corner monument:

A 11" dead 10' stub of Douglas fir, with partly healed blaze, bears N 68 1/2° E, 33.0'. (Survey I-153-C).
A 11" dead, uprooted white fir, with partly healed blaze, bears S 15° W, 38.2' to root hole. (Survey I-153-C).

Marked 4 new bearing trees:

A 6" white fir bears N 22° W, 14.6', scribed 1/4 S32 BT.
A 18" Englemann spruce bears N 5 1/2° E, 94.5', scribed 1/4 S32 BT.
A 6" white fir bears S 36° W, 14.2', scribed 1/4 S5 BT.
A 6" white fir bears S 62 1/2° W, 19.8', scribed 1/4 S5 BT.

Placed bearing object signs on all bearing trees.

Set steel fence post East of corner and attached a witness corner sign.

There is a North-West fence line 5' East of corner, and a fence corner with fences East, West, and South, 65' North of the corner.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>Will. R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 9-21
Rec'd By KX
No. 91-25-C

☆ GPO-798-276