


2-9

History of original corner establishment:

The original survey was made by Wm. H. Odell, US Deputy Surveyor under contract No. 114, Dated July 2, 1866. He set a post for the section corner common to sections 4, 5 & 32, 33. He set the following bearing trees:
A fir 20" dia. bears S 59 W, 19 lks.
A fir 15" dia. bears S 40 E, 59 lks.
A fir 20" dia. bears N 60 E, 40 lks.
A fir 18" dia. bears N 3 W, 9 lks.



Description of corner evidence found:

I found the remnant of a face with the scribing N R 37 E S lying by a four way fence corner post and a stone set by the post with 6 notches on the south face and an x on the top of the stone. After tying this stone to my extensive co-ordinate system, I found the position to be harmonious with the surrounding evidence and found corners in the area, thus I determined the stone to be a perpetuation of the original section corner even though I could not find any recorded record of the stone.

Description of monument and accessories I established to perpetuate the original location of this corner:

None



Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19....
 by
 (COUNTY OFFICIAL) (DEPUTY)