


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-3

History of original corner establishment: Corner established by Robert F. Omeg, U.S. Deputy Surveyor, under his Contract No.761, dated June 16, 1905. Surveyor General records state: Set a basalt stone 15x10x6 ins. 10 ins. in the ground for 1/4 sec.cor.marked 1/4 on N. face; from which: A pine 24 ins. diam. bears S36°E, 310 lks dist marked 1/4S7 BT.



A.J.Lommasson remonumented the N & S quarter-section corners of Sec. 7 in 1971...No certified record of land corner monumentation was found in County records. However, the Umatilla National Forest has a land corner card on file for each corner prepared by J.W.Blom in April 1972, and Blom's recovery record states: A basalt stone, scribed 1/4 on one side and a mound of stone and a B.T., 36" pine, bears S38°E. Approx. 200 ft dist. with the face partially chopped out & some scribing visible and legible. (Set) 2" pipe, 36" long with bottom flared and a 3" bronze disk brazed to the top, 24" into the ground. The original basalt stone is set next to the pipe with the original scribed 1/4 visible and legible. New BT is a 28" red fir bearing S40°W, 74 ft dist marked 1/4S7 BT. BT poster on both BT's. Location poster and yellow attention poster on the new BT.

Description of corner evidence found:

Found a 15x9x5" basalt stone with "1/4" alongside monument,
 A 3" brass cap on 2 1/2" galvanized iron pipe protruding 10" from a mound of stone.
 A 40" ponderosa pine brs S38°E, 207.8' with scribes visible on opened blaze.(OBT) A 28" douglas fir brs S40°W, 70.8' with healed blaze. (Lommasson BT)

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained monument by mounding more stone around the monument.
 I etched Township and Range on monument with pocket knife.

New bearing trees established:
 A 24" douglas fir bears N65°W, 171.1' scribed 1/4S6 BT.

New bearing tree has brass washer stamped PLS 1106 nailed to face of blaze. Set steel fence post West of corner and attached sign 54-4.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly maintained to USFS standards by me on August 12, 1988.

Note: Attached signs 54-3 and 54-4 and painted face of blaze and 6" red band around each bearing tree.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

Office of..... County Surveyor..... County of..... Umatilla.....
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 17th day of..... October..... 1988
 David N. Lommasson..... by..... Katherine K. Amberg.....
 (COUNTY OFFICIAL)..... (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 10-88
 Rec'd By [Signature]
 No. 88-64-B