


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-4

History of original corner establishment:

None. Corner established with this survey.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At position determined by survey...

Set 2½" aluminum cap on 2½" x 30" aluminum pipe 22" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post South of corner with signs 54-9 & 54-2 attached. Cap marked as shown in corner diagram.

There are no trees within limits, so I marked 2 bearing objects as follows: A 18"x12"x12" above ground point on a large rock outcrop brs S31°W, 115.1' marked "XBO" on East face. Bearing object is near the Southeast edge of the rock outcrop, which is about 50' E-W dimension & 200' N.S. dimension.

A 6'x6' flat spot on the same rock outcrop, at the East edge of the outcrop, brs S52½°W, 110.1' marked "XBO" on top. This area was marked because it offers one of the only smooth, flat spots on the outcrop. Painted the "XBO" marks in red paint.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly established by me on September 2, 1988.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of County Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 17th day of October, 1988
David H. Kumbier by Kathleen Amosberry
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

Date 10-88

Rec'd By KH

No. 88-64-B