

Index

File No. G-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 4 N 38 E

R.D. Walla Walla County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T 4 N R 38 E

C 1/4 • S 7

1988

PLS 1106

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER MONUMENT FOUND

None. Corner established with this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner located on built up ground between two branches of South Fork Walla Walla River. Corner is visible from trail 200' to the North of corner.

Signature
Willie R. Wells

Title
Land Surveyor

Division
Headquarters
Pendleton, Or.

Date
8-31-88

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position determined by survey...

Set 2½" aluminum cap on 2½" x 30" aluminum pipe 20" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post South of corner with signs 54-9 & 54-2 attached. Cap marked as shown in corner diagram.

Compass declination 14° East to match true bearings.

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 8" white fir brs S53½°W, 45.4' scribed C1/4S7 BT.

A 18" white fir brs N67½°W, 101.3' scribed C1/4S7 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 to each BT and painted face of blaze & 6" red band around each BT.

Work Done By W.R. Wells Title Land Surveyor Date 8-31-88 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared ? Yes XXXX Filed At: County Surveyor Date

REMARKS

Index File No. G-3 T. 4 N. 38 E

W. M.

Tract or Surv. No.

Cor.