


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-1

History of original corner establishment:

None. Corner established with this survey.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At position determined by survey...

Set 2 1/2" aluminum cap on 2 1/2" x 30" aluminum pipe 24" in ground to bedrock & surrounded with mound of earth only. Set 6' fence post South of corner with signs 54-9 & 54-2 attached. Cap marked as shown in corner diagram.

New bearing trees established:

A 15" douglas fir brs EAST, 40.4' scribed S1/16S7 BT.
A 14" douglas fir brs N35 1/2° E, 19.9' scribed S1/16S7 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 to each BT and painted face of blaze & 6" red band around each BT.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly established by me on August 30, 1988.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of County Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 17th day of October, 1988
David H. Kumberson by *Kathleen Ann Bruce*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor
Date 10-88
Rec'd By *[Signature]*
No. 88-64-B