

OREGON CORNER RESTORATION FORM

Section: 13 & 24
Township: 4 North
Range: 37 East, W.M.
County: Umatilla
Date: 08/06/2000

Corner Designation: N-25, Section corner common to Sections 13 & 24, T.4 N. R 37 E. & Sections 18 & 19, T.4 N. R. 38 E.

Previous Renewals/Surveys, etc.: This corner was originally set by U.S. Deputy Surveyor George S. Pershin, under his contract No. 304 dated September 19, 1878. The Surveyor General's notes state "set Basalt stone 12x10x5 and drove stake on SW face of mountain for corner to Sections 13, 24, 18 and 19 raised mounds of stone around stone and stake in lieu of pits."

Robert F. Omeg revisited this corner as part of his resurvey of the East line of the Township under his contract No. 761 dated June 19, 1905. The Surveyor General's notes state "Intersect the old cor. for Secs. 13, 18, 19 & 24, which is a basalt stone, 12x10x5 ins. marked as described by the surveyor general. The mound is destroyed. I re-establish the cor. at the same point as follows: set a lava stone, 12x8x6 ins. 8 ins. in the ground for cor of secs. 13, 18, 19 & 24, marked 3 notches on N. and S. edges, and raised a mound of stone, 2 ft. base and 1 ft. and a half high W. of Cor."

U.S. surveyor Otis O. Gould under special instructions, group 234 dated July 11, 1939. His notes state "The cor. of secs. 13, 18, 19 and 24 which is a basalt stone 14x12x6 ins. firmly set, marked with 3 grooves on the N. and S. faces. At point for corner set and iron post 3 ft long 2 ins. diam. 27 ins. in the ground, with the original stone deposited at the base."

Monument(s) & Accessories Found (Condition & Source): Found a 2" iron pipe with a 2 1/4" brass cap stamped as shown per the resurvey by Otis O. Gould, The monument is firmly set and protrudes 9" from the ground.

Monument Detail: US GENERAL LAND OFFICE SURVEY

T4N
R37E R38E
S13 S18
+
S24 S19
1939

Monument Set (Procedures & Description): Rebuilt a mound of stone 3 feet in diameter 1 1/2 feet high 3 feet South of the corner.

New Accessories: Set 6' carsonite post 5' North of the corner with survey monument and forest boundary stickers attached. Set 5/8"x30" rebar reference monuments (RM) with 1 1/2" aluminum caps stamped as shown, as follows:

N40°E 14.8 feet S34°E 18.6 feet S30°W 21.5 feet N75°W 20.1 feet

All RM's are driven to refusal and surrounded with a mound of stone, and have a 6 foot steel fence post set alongside with bearing tree and survey monument signs attached.

Location & Comments: This corner is located on a barren, Southwesterly facing slope overlooking Tamarack Basin and is a considerable hike from the nearest road.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204
Walla Walla WA 99362

Party Chief: Josh Martin

Notes: Josh Martin Witness: Ryan Laughery

Surveyor's Seal



RENEWS 12/31/01

RECEIVED BY
Umatilla County Surveyor
Date 12-00
Rec'd by SM
No. 00-256-C

12/15/00