

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by Frank Campbell under G.L.O. contract number 468 dated April 12, 1883.

Surveyor General's records state:

Set a basalt stone 16" x 10" x 5", 11" in the ground for the corner to secs 21, 22, 27 & 28 marked with 2 notches on S and 3 notches on E edges from which:

- A fir 18" dia bears N 19° E., 84 lks dist marked T 4 N R 38 E S 22 BT
- A fir 30" dia bears S 10° E., 82 lks dist marked T 4 N R 38 E S 27 BT
- A fir 30" dia bears S 30° W., 52 lks dist marked T 4 N R 38 E S 28 BT
- A fir 16" dia bears N 42° W., 138 lks dist marked T 4 N R 38 E S 21 BT



R-13

Description of corner evidence found:

Found a basalt stone 17" x 10" x 6" in place with an X chisled on top point and 2 notches on S and 3 notches on the E edges.

A rotten stump bears S 10° E., 54.1 ft. (82 lks) for sec 27 BT

A rotten stump bears S 30° W., 34.3 ft. (52 lks) for sec 28 BT

No trace of secs 21 & 22 BT.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long in earth and rock mound with a 6' steel fence post with sign 54-4 attached 4' south of corner.

new bearing trees:

- A fir 8" dia bears S 13° W., 30.0 ft dist marked T 4 N R 38 E S 28 BT
- A fir 8" dia bears S 59° E., 34.0 ft dist marked T 4 N R 38 E S 27 BT
- A fir 12" dia bears N 28° W., 29.5 ft dist marked T 4 N R 38 E S 21 BT
- A spruce 14" dia bears N 27° E., 43.8 ft dist marked T 4 N R 38 E S 22 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.

Note: I buried the stone on north side of brass cap monument.



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 26 day of August, 1976  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)

Q-1237R