

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N , R 38E. , W.M.


Corner Code No. R-15

Note: Monument marked as shown below

History of original corner establishment:

Corner was established by Frank Campbell under Contract No. 468, dated April 12, 1883. The original notes state: Set a basalt stone 10 ins. X 10 ins. by 8 ins. 7 ins. in the ground for 1/4 sec cor marked 1/4 on North face, from which: A tamarack 6 ins. diam bears N 10° E. 17 lks dist. marked 1/4 S BT. An alder 4 ins. diam bears S 05° W., 50 lks dist. marked 1/4 S BT.

This corner was declared lost in 1976 and re-established by J.D. Hanley. Certificate Record No. 8-1238 states: Set a 2 1/2" brass cap on a 2" iron pipe 31" long in rock mound near top edge of talus slide with a 6 ft. steel fence post 6 ft. north with sign 54-4 attached. New bearing trees: A fir 8" diam. bears S 49° E., 35.5 ft. dist. marked 1/4 S 27 BT. A fir 14" diam. bears N 89° W., 60.5 ft. dist. marked 1/4 S 22 BT.



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe projecting 3" out of a talus slide from which:

A 12" douglas fir bears S 48°E, 35.5' with healed double blaze. (Hanley) A 17" douglas fir bears N 89°W, 60.5' with healed double blaze. (Hanley)

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained monument by mounding with stone.

Marked 2 new bearing trees:

A 8" douglas fir bears N 47 1/2°W, 57.7' scribed 1/4 S22 BT. A 14" white fir bears S 27 1/2°E, 48.0' scribed 1/4 S27 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around all bearing trees.

Set steel fence post North of corner with a 54-9 sign attached.

Corner located near top edge of talus slope about 100' West of a 100 ft. high rim.

REGISTERED PROFESSIONAL LAND SURVEYOR

Willis R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.... by..... (COUNTY OFFICIAL)

(DEPUTY) RECEIVED BY

Umatilla County SURV-VOJ

Date 1-92

Rec'd By AR

No. 92-01-R