

R-17


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Frank Campbell under G.L.O. contract number 468 dated April 12, 1883.

Surveyor General's records state:

A tamarack 8" dia. which I mark T 4 N S 2 3 on NE, R 3 8 E S 2 6 SE, S 2 7 on SW, and S 2 2 on NW faces with 2 notches on S and E ges for corner to secs 22, 23, 26 & 27 from which:



- A tamarack 11" dia. bears N 21° E., 10 lks. dist. marked T 4 N R 3 8 E S 23 B T
- A tamarack 12" dia. bears S 31° E., 25 lks. dist. marked T 4 N R 3 8 E S 26 B T
- A tamarack 12" dia. bears S 25° W., 13 lks. dist. marked T 4 N R 3 8 E S 27 B T
- A fir 10" dia. bears N 51° W., 24 lks. dist. marked T 4 N R 3 8 E S 22 B T

R-17

Description of corner evidence found:

- A larch 12" diam. bears S 31° E., 16.5 ft.(25 lks) with visible scribing
- A larch 13" diam. bears S 25° W., 8.6 ft.(13 lks) with no visible scribing
- A stump 12" diam. bears N 21° E., 6.6 ft.(10 lks) with rotting tree alongside with visible scribing.

Description of monument and accessories I established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long 4" above the ground with a 6' steel fence post 4' north with a sign 54-4 attached.

new bearing trees:

- A fir 9" diam. bears N 68° W., 27.0 ft. dist. marked T 4 N R 3 8 E S 22 B T
- A spruce 18" diam. bears N 47° E., 21.8 ft. dist marked T 4 N R 3 8 E S 23 B T
- A spruce 12" diam. bears S 38° W., 31.4 ft. dist. marked T 4 N R 3 8 E S 27 B T

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of... Surveyor County of... Umatilla
 State of... Oregon , I hereby certify that the within instrument was filed in this office
 for record on the 26 day of Aug., 1976
 by
 (COUNTY OFFICIAL) (DEPUTY)