


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX: S-5

History of original corner establishment:

A. Corner not established by GLO



Allen T. Lommasson registered land surveyor in the state of Oregon license number 422 set a 3/4 inch dia by 30 inch long black iron pipe at the 1/16 corner in October 1972, as recorded as survey number H-90 records of Umatilla County, Oregon.

Description of corner evidence found:


B. MONUMENT FOUND:

found a 3/4 inch dia by 30 inch long iron pipe 10 inches exposed

ACCESSORIES FOUND: none

Description of monument and accessories I established to perpetuate the original location of this corner:

C. I set in place a 2.5 inch dia. by 30 inch long aluminum monument at the locus of the iron pipe and bound the iron pipe flush with the ground at the east edge of the aluminum monument. The aluminum monument is set 26 inches in the ground. I mark the cap:



NEW ACCESSORIES ESTABLISHED with magnetic declination of 21 deg. East 14" true fir bears N16E at 29.3 ft scribed "N 1/16 S29 RT" 15" spruce bears S84E at 21.5 ft scribed "N 1/16 S29 RT"

Note: did not place a RT in section 30 due to poor tree conditions

Painted red band around each bearing tree. Placed brass washer marked "PLS 2060" at base of blaze on each new RT Placed USDA Forest Service metal signs 54-3 (RT) and 54-4 (ATTENTION) on each bearing tree. Placed 54-9 (LSM) and 54-2 (PROPERTY BOUNDARY) on steel fence post set north of corner.

Office of Survey Dept County of Umatilla State of OR I hereby certify that the within instrument was filed in this office for record on the 17 day of November 1989 David A. Bumbear by Kathleen K. Amberg (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 11-89

Rec'd by KA

No. 89-107B

REGISTERED PROFESSIONAL LAND SURVEYOR

Edwin A. Stryker

OREGON JULY 15, 1983 EDWIN A. STRYKER 2060