

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N , R 38E. , W.M.

Corner Code No. T-17  
Note: Monument marked as shown below

History of original corner establishment:

Corner was originally established by Frank Campbell under Contract No. 468 dated April 12, 1883. The original notes state:

Set a post 3 1/2 ft. long 3 ins. square with marked stone 24 ins. in the ground for 1/4 sec cor marked 1/4 on W face from which:


A tamarack, 13 ins. diam. bears N 53° W, 17 lks dist. marked 1/4 S BT.  
A tamarack, 12 ins. diam. bears S 60° E, 10 lks dist. marked 1/4 S BT.

In 1976, J.D. Hanley recovered the two original bearing trees at record bearings and distances and re-established the corner. Certificate Record No. G-1240-R states:

Set a 2 1/2" brass cap on a 2" iron pipe 31" long in earth mound 6" above the ground with a 6" steel fence post along side with a sign 54-4 attached.

New bearing trees:

A larch 14" diam. bears S 40° E., 20.5' marked 1/4 S BT with a sign 54-3 attached 6" below a band of red paint and a brass washer marked RPE 2808 nailed flush with BT blaze.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe projecting 4" out of the ground from which:

A 18" western larch bears N 53°W, 11.2' with a healed blaze. (Original bearing tree).

A 13" snapped off western larch bears S 60°E, 6.6' with scribes visible on a previously opened blaze. (Original bearing tree).

A 14" dead western larch snag bears S 18°E, 20.5' with scribes visible on a partly healed double blaze. (Hanley's record bearing was S 40° E).

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained by cleaning up around monument and mounding with earth. Set steel fence post to the North with sign 54-9 attached.

Marked 4 new bearing trees:

- A 23" western larch bears N 14 1/2°E, 63.4' scribed 1/4 S26 BT.
- A 25" Englemann spruce bears N 85 1/2°E, 41.5' scribed 1/4 S26 BT.
- A 6" Englemann spruce bears N 62°W, 19.2' scribed 1/4 S27 BT.
- A 9" Englemann spruce bears S 54°W, 4.1' scribed 1/4 S27 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around all bearing trees.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL)

(DEPUTY)  
RECEIVED BY

Umatilla County Surveyor

Date 1-92

Rec'd By AK

No. 92-02-R