

T-17

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by Frank Campbell under G. L. O. contract number 468 dated April 12, 1883.

Surveyor General's records state:

Set a post 3 1/2 ft. long 3 ins. square with a marked stone 2 1/4 ins. in the ground for 1/4 sec cor marked 1/4 on W face from which:

A tamarack 13" diam. bears N 53° W., 17 lks dist. marked 1/4 S BT
A tamarack 12" diam. bears S 60° E., 10 lks dist. marked 1/4 S BT



T-17

Description of corner evidence found:

A larch 18" diam. with healed blaze bears N 53° W., 11.22 ft(17 lks) dist. with 1971 BT tag.

A larch 14" diam. with previously opened blaze bears S 60° E., 6.6 ft(10 lks) dist. with visible scribing. 1/4 S.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long in earth mound 6" above ground with a 6' steel fence post along side with a sign 54-4 attached.

new bearing trees:

A larch 14" diam. bears S 40° E., 20.5 ft. dist. marked 1/4 S BT with a sign 54-3 attached 6" below a band of red paint and a brass washer marked RFE 2808 nailed flush with BT blaze.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of Aug. 1976
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)