

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:
 Center West 1/16 Corner, Sec. 30, T4N, R38E, WM.
 Corner not previously set.

Index: T-2

1	DIAGRAM	1
1		1
1	T4N R38E	1
1	1	1
1	W ---	1
1	16	1
1	C-----C	1
1	S30	1
1	1995	1
1	PLS 852	1
1		1

Description of corner evidence found:
 None

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 2 1/2" x 30" aluminum pipe 26" in the ground. I stamped the cap as shown in the diagram above. A 30" mound of stone is placed around the monument.

I set the following new witness trees:

A 16" dbh White Fir bears S41°40'W, 23.4', scribed CW 1/16 S30 BT.

A 24" dbh White Fir bears S42°05'E, 10.4', scribed CW 1/16 S30 BT.

The bearings are based on traverse control stations and are true.

A brass washer stamped ORLS852 and WALS 13922 is attached between the letters B and T with a brass screw on each new tree. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red stripe is painted around each tree at chest height.

This work was finished August 14, 1995 and witnessed by Stephen Haddock.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

David L. Haddock

OREGON
 JULY 12, 1968
 DAVID L. HADDOCK
 852

Office of Survey County of Umatilla
 State of OREGON, I hereby certify that the within instrument was filed
 in this office for record on the 23rd day of October, 1995.

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 10-95

Rec'd by KK

No. 95-179-B