

USDA-FOREST SERVICE

INDEX

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Cor.

FILE NO. T-3

Survey No.

No.

T. 4 N R. 38 E R.D. Walla Walla

County Umatilla

Merid. Willamette N.F. UMATILLA

State Oregon

1

CORNER DIAGRAM T4N R38E 1 DESCRIBE CORNER MONUMENT FOUND

1 1 1 Corner not previously set.

1 C--S30 1

N 4 1

1 1995 1

2

1 PLS 852 1 DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

1 Corner not previously set.

PHOTO IDENTIFICATION DATA 1

Photo No. 1

Filed At. 1

Object Ident. 1

Ident. By 1

Signature 71

3

PLANE COORDINATE POSITION DATA 1 DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

State Zone 1 The corner may be reached by traveling the McIntyre Road from the Tollgate Store 0.8 mile.

X 1 The corner is 100' east of the road at the southerly edge of a small opening.

Y 1

Estab. By 1

Agency 81

4

Signature

Title
Surveyor

Division

Headquarters
Pendleton, OR

Date
9-04-95

FS-7100-52 (3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" X 30" aluminum pipe and cap 26" into the ground with a 30" mound of stone. Stamped the cap as shown in the corner diagram on the opposite side of this card.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Set new bearing trees.

A 9" dbh Douglas Fir bears N70°24'W, 21.6' scribed C 1/4 S30 BT.

A 9" dbh White Fir bears N79°35'E, 41.7' scribed C 1/4 S30 BT.

A 14" dbh White Fir bears S51°33'E, 85.0' scribed C 1/4 S30 BT.

A 8" dbh Alpine Fir bears S13°18'E, 20.0' scribed C 1/4 S30 BT.

A brass washer stamped ORLS 952 and WALS 13922 is nailed between the letters B and T on each tree with a brass screw. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red band is painted around each tree at

10

Work Done By. David L. Haddock	Title Land Surveyor	Date 8-16-95	State Registration No.
Certified Cor. Record Prepared?	x Yes	No	or Agency PLS 852
		Filed At: Umatilla County Surveyor	Date 9-95

11

REMARKS

12

Index File No. T-3 T. 4 N. R. 38 E. M. Willamette Tract or Surv. No. Cor. 13