

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: U-2

Southwest 1/16 Corner, Section 30, T4N, R38E, W.M.

Corner not previously set.

1	DIAGRAM	1
1		1
1	T4N R38E	1
1	1	1
1	SW---.S30	1
1	16	1
1	1995	1
1	PLS 852	1
1		1
1		1
1		1

Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 2 1/2" x 30" aluminum pipe 26" in the ground. I stamped the cap as shown in the diagram above. A 24" collar of stone is placed around the monument.

I set the following new witness trees:

A 24" dbh Engleman Spruce bears N47°23'W, 70.2', scribed SW 1/16 S30 BT.

A 14" dbh White Fir bears N16°12'E, 55.1', scribed SW 1/16 S30 BT.

The bearings are based on the traverse control stations and are true.

A brass washer stamped ORLS852 and WAL5 13922 is attached between the letters B and T with a brass screw on each new tree. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red stripe is painted around each tree at chest height.

This work was done August 15, 1995 and witnessed by Stephen Haddock.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1988
DAVID L. HADDOCK
852

Office of Survey Dept. County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed
in this office for record on the 23rd day of October, 1995.

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 10-95
Rec'd By KK
No. 95-179-B