


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX: U-7

History of original corner establishment:

A. Corner not established by GLO



Description of corner evidence found:

B. MONUMENT FOUND:

none

Description of monument and accessories established to perpetuate the original location of this corner:

C. I set in place a 2.5 inch dia. by 30 inch long aluminum monument 26 inches in the ground. No stones available.

I mark the cap:



NEW ACCESSORIES ESTABLISHED with magnetic declination of 21 deg. East

8" true fir bears S74W at 20.6 ft scribed "CS 1/16 S29 RT"  
 7" true fir bears S13E at 19.4 ft scribed "CS 1/16 S29 RT"

Painted red band around each bearing tree.  
 Placed brass washer marked "PLS 2060" at base of blaze on each new RT  
 Placed USDA Forest Service metal signs 54-3 (RT) and 54-4 (ATTENTION) on each bearing tree.  
 Placed 54-9 (LSM) and 54-2 (PROPERTY BOUNDARY) on steel fence post set 5 feet north of corner.

Office of Survey Dept. County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office  
 for record on the 6th day of November, 1989  
David A. Kumbrian by Kathleen K. Ambrose  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 11-89  
 Rec'd by RT  
 No. 89-107-B

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
Edwin A. Stryker  
 OREGON  
 JULY 15, 1983  
 EDWIN A. STRYKER  
 2060