

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. V-25

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, in 1879.

The original notes state:

Set fir post on South slope for corner to Sections 25, 36, 30, & 31.

- A tamarack 14 in. dia. bears N 10° E 27 lks dist.
- A fir 6 in. dia. bears S 48° E 29 lks dist.
- A fir 10 in. dia. bears S 52° W 53 lks dist.
- A fir 6 in. dia. bears N 45° W 34 lks dist.

This corner was recovered and re-monumented by Otis Gould, GLO Surveyor in 1939. Gould re-monumented with a standard GLO brass cap on a galvanized iron pipe, as explained in recorded field notes.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 2 1/2" G.L.O. brass cap on a 2" O.D. galvanized iron pipe 8" out of ground, from which:

- A 18" western larch stump bears N 04° E, 15.4' with traces of face and axe marks visible. (Pershin bearing tree)
- A 18" white fir stump bears S 65° W, 26.4', with heald over blaze. (Gould bearing tree).

Description of monument and accessories | established to perpetuate the original location of this corner:

Cleaned up around monument and rebuilt earth mound.

Marked 4 new bearing trees:

- A 7" white fir bears N 22 1/2° E, 23.7', scribed T4N R38E S30 BT.
- A 14" white fir bears S 42 1/2° E, 32.9', scribed T4N R38E S31 BT.
- A 10" white fir bears S 62 1/2° W, 39.0', scribed T4N R37E S36 BT.
- A 20" Englemann spruce bears N 38 1/2° W, 32.4', scribed T4N R37E S25 BT.

Placed bearing object signs on bearing trees, and witness corner signs on back of trees.

Set steel fence post North of corner and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

★ GPO-798-276

Date 9-9/

Rec'd By KR

No. 91-25-C