

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 4 N R 38 E

History of original corner establishment:

Corner originally established by Frank W. Campbell under contract # 468 dated April 12, 1883. Set a 3 1/2 foot by 3 inch post 24 inches in ground marked 1/4 S on N face, Also a marked stone.

From which:

- a 24" tamarack bears N 26° W 50 lks
a 28" tamarack bears S 22° E 52 lks



In a U.S. Dependent Resurvey by Otis O. Gould in August 1939 he set a 3 foot by 1 inch iron pipe 27" in ground with a brass cap marked as diagram. from which:

- a 12" pine bears N 76° W 16 lks (10.6 ft)
a 10" spruce bears S 13 1/2° E 25 lks (16.5 ft)

Description of corner evidence found:

Found 1" iron pipe with brass cap stamped as diagram from which:
a 12" down pine root hole bears N 76° W 10.6 ft 28 visible on blaze
a 27" spruce stump bears S 13 1/2° E 34.3 ft (52 lks) no marks visible

Description of monument and accessories I established to perpetuate the original location of this corner:

I drove a steel fence post 3 feet west and attached USFS 54-4 sign.
New bearing trees:
a 18" fir bears S 61° W 19.6 ft. scribed 1/4 S 33 BT
a 10" fir bears N 57° W 12.4 ft. scribed 1/4 S 28 Bt
I nailed Alum tags stamped 951 to bottom of blazes and painted blazes red.
Painted red band around BT's and nailed USFS 54-3 and 54-4 signs to them.

I hereby certify the above corner location was perpetuated as herein described in July, 1985

Jud Coppock, Witness

REGISTERED PROFESSIONAL LAND SURVEYOR

G. Dennis Edwards

OREGON JULY 18, 1971 G. DENNIS EDWARDS 951

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....
(COUNTY OFFICIAL) by (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 8-6-85
Rec'd By KA
No. 85-97-R
(85-95-C)